

**DOEACC SOCIETY**  
**Gorakhpur Centre**  
(Construction & Maintenance Section)

Annexure-I

**Tender-Form (Schedule of work)**

**Name of Work:** **“Partition work for PE/Instrumentation/Hardware Lab & UPS wiring in PE Lab”**

**FILE NO:** DOEACC/GKP/200/C/2011-12/01

**Location:** Institute Bldg. (First Floor)

S.N.	Item Description	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1.	Providing & fixing double skin plywood partition (Partly glazed) upto 12’ height by making, Kail wood batten of size 2’’x 2’’ frame work, panel size 2’x2’c/c (max.), fixing of commercial ply 4.0mm thick pasted with 4.0mm thick Veneer both side of partition in groove pattern and rounded teak wood beading of 2.5’’x1’’ size at top & open side of the partition, making ventilation panel and fixing anodized aluminium mesh of approved pattern/design, good quality sprit polishing with nice finish, complete as per drawing/design and instructions of the Engineer-In-Charge.	1100	sqft		
2.	Extra for providing door shutter with necessary hinges, additional wood and Aluminium fittings in the partition detailed in item No. 2 above.	91	sqft		
3.	Providing and fixing PVC Casing & Capping on wall surface as per instructions of Engineer-In-Charge complete. (a) 25x10mm size	50	RM		

4.	Supplying and drawing following size of PVC insulated copper conductor, single core cable in the existing surface/recessed PVC/Steel Conduit/ PVC casing & capping as required. (a) 1x1.0 Sq. mm (b) 2x1.5 Sq. mm (c) 2x2.5 Sq. mm (d) 2x6.0 Sq. mm	50 30 20 06	RM RM RM RM		
5.	S/F of sheet steel single-phase enclosure for DP MCB with earth terminal etc. fixed on surface complete in all respect.	1	No.		
6.	Supply and fixing of switch board, teak wood base with white phylum sheet top/ acrylic base board, approx. size 175x100 mm consisting of 3 No. 5 pin 6A socket & 1 common piano type switch 6 A of approved ISI make including internal connection, fixing on wall/partition etc. complete.	22	No.		
7.	Supply and fixing of DP MCBs (ISI Make) 40 A, 10 KA complete.	01	No.		
8.	Supply and fixing of SP MCBs (ISI Make) 40 A, 240 V, 10 KA complete.	01	No.		
			<b>Total</b>	<b>Rs.</b>	

Rupees in words:.....  
.....

**Signature of Contractor**

Name:

Date:

Address:

Place: